

GB-7575F-1804

Model Specifications	40 HP	7" Cylinder	63" Stroke
<ul style="list-style-type: none"> • Feed opening • Bale Chamber • Bale Size expandable • Bale Weight • Tension Cylinder • Machine Weight • Main Baler Body Frame • Cutting Knife Replaceable • Auto Tier • Number of Ties • Wire Arrangement • Ram Face Pressure • Tension Force • Tension Type • Cycle Time (No Load) • Cycles Per Minute • Tie Cycle • Production (O.C.C.) 			40" x 28" 30" x 30" x 63" 30" x 30" x 47" (Adjustable) Up to 1,000 lbs. 7" Diameter 7" Stroke 17,500 lbs. SS41 Tool Steel Scatter Cutter Hydraulic Actuated Inserter 4 50, 100 lb. spools 130 PSI 200 tons 4-Way Free Floating Clamber 8.7 Sec. 7 19 – 35 Sec. 7-10 TPH

Hydraulic System

<ul style="list-style-type: none"> • Hydraulic System • Oil Reservoir • Hydraulic cooling • Hydraulic filtration • Hydraulic Pump Brand • Valve Brand 	Regenerative 148 Gallons 560 Liters Air Cooling Suction Filter DENISON VICKERS
-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-----------------------------------------------------------------------------------------------

Electrical System (UL)

<ul style="list-style-type: none"> • PLC 	MITSUBISHI
---------------------------------------------------------	------------

- Operator Interface
- Main Motor Control
- Controller Brand
- UL Standard

Human Machine Interface
STAR/DELTA
SIEMENS

After Service System

- Complete operations manual. Including installing, operations, maintenance, electrical control diagram, hydraulic circuit diagram, and parts list diagram.

Remarks

- One year warranty under normal use and maintenance, except for consumables.
- Excludes: Foundation, Electrical wiring outside of machine, hydraulic oil (Shell Tellus R68 or Mobil D.T.E. 26)
- Excludes: steel wire (2.7mmDIA) annealed twice, cyclone and conveying pipes and slat conveyor work, slat conveyor COVER PLATE
- Excluded: Machine installation and test running.